

A-918  
ALERO C  
1/2

Walls shall have two (2) coats of paint. Doors and windows shall have two (2) coats of paint both sides, unless otherwise noted. PAINT ALL WALLS AS PER FINISH SCHEDULE.

Ceiling Tile shall be painted, one coat Luminal satin paint, ACRYLURENE No. 21801 White, as manufactured by Luminal Paint Company or approved equal. All tile should be dropped and painted on grid.

PAINT DOORS, FRAMES AND CONNECTORS AS PER FINISH SCHEDULE.

#### WALL COVERING

Prime and seal all surfaces scheduled for wall covering as per finish schedule.

All work shall be in accordance with the manufacturer's printed instructions.

#### Closet Shelf and Clothes Pole

Closet shelf shall be 3/4" thick particle board supported by continuous angle on three sides. Paint shelf and angle to match walls. Clothes pole shall be 1" O.D. 20 Ga. chrome plated steel tubing No. T600 as manufactured by Plaza Towel Holder Co. or approved equal.

#### MATERIALS FURNISHED BY THE AUTHORITY

The authority will furnish to the contractor the materials in the quantities as shown below for installation in the permanent construction. The furnishing and installation of any materials in addition to the quantities shown shall be the responsibility of the contractor.

Materials can be obtained at Tower B basement level 294. Material storage area is open daily from 7:30 a.m. - 12:00 noon and 1:00 p.m. - 3:30 p.m. For material withdrawals, call (212) 466-4154 at least 24 hours in advance.

All excess material furnished by the Authority not used in the permanent construction shall be returned as directed by P.A. ENGINEER.

All components for gypsum wallboard partition

- Ceiling and floor runners for salvaged (movable gypsum wallboard) partition
- Vinyl asbestos floor tile
- Wall Base  
(a) Straight  
(b) Cove

- Set III 5 (2) pairs butts, (1) latchset, (1) domestop, (3) silencers
- Set IV 2 (4) pairs butts, (2) domestops, (1) latchset, (2) silencers

Aluminum Seals: 3'-0" Hollow metal doors and frames

Door	Description	Qty/Set
1	3'-0" x 8'-0" INTERIOR	III
2	" " " "	III
3	" " " "	II
4	(2) 2'-0" x 5'-0" INTERIOR	IV
5	3'-0" x 5'-0" REAR ENTRY	I

#### INSTALLATION OF MATERIALS

##### MOVABLE GYPSUM WALLBOARD PARTITIONS

The installation of movable gypsum wallboard partitions shall be in accordance with currently printed manufacturers' instructions and recommendations unless otherwise directed by RCL/Design Group Inc.

##### HARDWARE

Finish hardware installation shall conform to the manufacturers requirements. Installation shall be in a neat and skillful manner, with all components operating properly. All knobs, handles, pulls and other exposed items shall be suitably wrapped and protected as soon as they have been installed and the protection shall remain until the acceptance of the work.

Immediately preceding final inspection all hardware shall be cleaned carefully to remove which will in no way damage it.

- Knobs - Stanley PHE 179 R 1 1/2" x 4 1/2"  
Mortise Lockset - Corbin #124-200  
Latch Set - Corbin #82-410  
Closer - Corbin #600-500  
Flush Bolts - Corbin #284-100 1 1/2" x 1 1/2" 19.  
Domestop - Corbin #773-100  
Coordinator - Von Duprin #1100  
Silencers - Corbin #20  
Aluminum Saddles - Teco Weatherstripping Co., Inc. #100-100

After erection, exposed surfaces, corners, and all painted areas adjacent to the same shall be touched up.

WALL BASE

Wall base shall be approved type cor. below top of base. base shall be finished joints shall be at least 1/4" distance from a

#### ACOUSTIC CEILING

Black iron carry supported by hangers, and all structural members required to add drapery pocket a

Ceiling tile shall be even plane, butt metal edge mould

MODIFY ACOUSTIC LAYOUT AS SHOWN

#### NOTES

- The work shall be performed otherwise re contractor Inc. and the
- Before commencing verify all field. Any brought to the Inc. and the
- Before commencing notify RCL/Design Group Inc. All exposed items shall be wrapped up with OAK directed by World Trade
- The contractor shall be responsible for the approval and the work
- The contractor shall be responsible for the removal of the floor
- The contractor shall be responsible for the construction of the Contract.

be one of the following:

by Davos & Reynolds, equal.

specifically manufactured on which it is to be

## SPECIFICATIONS

RCL DESIGN GROUP INC.